

# कार्यालय मेदिनीनगर नगर निगम।

ज्ञापांक ..... दिनांक .....

अतिअल्पकालीन कोटेशन/दर आमंत्रण सूचना संख्या 04/2018-19

मेदिनीनगर नगर निगम क्षेत्रान्तर्गत पर्यावरण एवं स्वच्छता के तहत सड़क के किनारे फ्लैक में Paver Block अधिष्ठापन तथा खुली नाली पर कौमर ड्रेन निर्माण करायी जानी है। जिसके लिए इच्छुक निर्माणकर्ता/आपूर्तिकर्ता/संवेदक सीलबन्द लिफाफे में अपना निविदा/कोटेशन दिनांक 14.09.2018 को 2.00 बजे अपराह्न तक नगर निगम कार्यालय में जमा कर सकते हैं। निविदा/कोटेशन के साथ GST,PAN, अनुभव प्रमाण पत्र, निबंधन प्रमाण पत्र, अद्यतन ITR साथ संलग्न करेंगे। निविदा को स्वीकार या अस्वीकार करने का अधिकार अधोहस्ताक्षरी को सुरक्षित रहेगा। सामान दर रहने पर आदेश एक से अधिक निविदादाताओं को दिया जाएगा। निविदा/कोटेशन उसी दिन अपराह्न 3.00 बजे नगर निगम कार्यालय में खोली जाएगी। कोटेशन समर्पित करने वाले कोटेशनदाता अथवा उनके द्वारा प्राधिकृत प्रतिनिधि कोटेशन खोलने के समय उपस्थित रह सकते हैं। आपूर्ति/निर्माण कार्य से संबंधित विवरणी कार्यालय सूचना पट एवं Website <http://udhd.jharkhand.gov.in> के नोटिस पर अवलोकन किया जा सकता है अथवा कार्यालय आवधि में कार्यालय से प्राप्त किया जा सकता है।

sdj -

कार्यपालक पदाधिकारी  
मेदिनीनगर नगर निगम

ज्ञापांक 3555 दिनांक 06/09/2018

प्रतिलिपि :- नगर निगम कार्यालय सूचना पट पर साट कर सूचनार्थ/ Website <http://udhd.jharkhand.gov.in> के नोटिस पर अवलोकन किया जा सकता है।

06/09

कार्यपालक पदाधिकारी  
मेदिनीनगर नगर निगम

Detail Model Estimate for construction of Paver block & Cover drain in Medininagar  
Municipal Corporation Area District- Palamau, Jharkhand

Sl. no.	Item of Work	Rate	Quoted Rate
1 5.1.1+5.1.2	Earth work in excavation in foundation trenches in ordinary soil (vide classification of soil Item – A and disposal of excavated earth as obtained to distance up to 50M including all lifts ,leveling, ramming the foundation trenches, removing roots of trees, shrubs all complete as per approved design building, specification and direction of E/I . 2x100'0"x6'0"x0'8" = 799.92 cft Over burden - @ 20% = 159.98 cft = 959.90 cft or 27.18 M <sup>3</sup>	120.53/M <sup>3</sup>	
2 5.1.10	Providing coarse clean sand in filling in foundation trenches or in plinth including ramming and watering in layers not exceeding 150mm thick with all leads and lifts including cost of all materials, labour, royalty and taxes all complete as per building specification and direction of E/I (Mode of measurement compacted volume) 2x100'0"x6'0"x0'4" = 400.00 cft or 11.33 M <sup>3</sup>	223.35/ M <sup>3</sup>	
3 SOR 2016 Page no. 34 110	Providing and laying 80mm thick made cement 16.68 interlocking paver block of m-35 grade made by block maching with strong vibratory by block compaction of as approved size .... Do.... 2x100'0"x6'0" = 1200.00 sft. or 111.52	1078/ M <sup>2</sup>	
4 5.3.2	Providing P.C.C. M-150 in nominal mix of (1:2:4) in foundation with approved quality of stone chips 20mm to 6mm size graded and clean coarse sand of FM 2.5 to 3 including screening shuttering mixing cement concrete in mixer and placing in position vibrating, striking curing taxes and royalty all complete as per building specification and direction of Engineer incharge. Side curt 2x100'0"x0'6"x0'5" = 4166.00 cft. or 1.18 M <sup>3</sup>	5358.83/ M <sup>3</sup>	
5 5.3.30.1	Providing pre Cast RCCm-200 with nominal mix of (1:5:3) in roof slab with approved quality of stone chips 20mm to 6mm size and clean coarse sand of F.M. 2.5 to 3 incieing sceening, shuttering, mixing, cement concret in mixer and placing in position, vibrations, striking, cering (but excluding the cost of reinforcement, taxes and royalty all complete, as per building specification and direction of E/I 2x100'0"x4'0"x0'6" = 400.00 cft or 11.33M <sup>3</sup>	5489.86/ M <sup>3</sup>	
6 5.5.5	Providing Tor steel reinforcement of 8mm, dia rods as per approved design and drawing excluding carriage of bars to work site, cutting, bending, and binding with annealed wire with cost of wire, removal of rust, placing the rods in position all complete as per building specification and direction of E/I 400 cft @ 2.5 kg/cft. = 1000.00 Kg or 1.00 mt.	63762/ mt	
	Total Rs.		
	Add carriage of materials @ 10% (+)		
	Add 12 % GST (+)		
	Add 1 % Labours (+)		
	Total Rs.		

06/09